Mobile Home DVX Vertical Co-Axial Direct Vent І 🔥 🐧



▶ 6-Year Limited Warranty on Tank and Parts

- Installed side mounted T&P valve
- Can be installed anywhere in the home
- Field convertible controls for natural gas or LP operation
- 3/4" hot and cold top connections
- Meets or exceeds National Appliance Energy Conservation Act (NAECA) requirements
- · Piezo ignitor easy light pilot
- Easily fits into a standard drain pan
- All models are certified for applications up to 7,700 feet above sea level.
- · Specially formulated lining
- Certified for manufactured (HUD) and modular construction

The Mobile Home Gas Direct Vent model is certified for manufactured home use, meets ANSI Standards for modular home construction and complies with HUD safety and construction standards.




Gas control is convertible from natural gas to liquid propane.

Energy Factor and Average Annual Operating Costs based on D.O.E. (Department of Energy) test procedures. D.O.E. national average fuel rate natural gas \$1.218/therm; LP \$1.87/gallon.

	PTION	FEATURES				DIMENSIONS					ENERGY INFORMATION			
Tank Gallo Capacity	n Height Description	Model Number	Thous. Nat.	Btu/h LP	Recovery in G.P.H. 90° Rise	First Hour Del. G.P.H.	Tank Diam.	Vent Height	Tank Height	Vent Size	Shipping Wt. (Pounds)	Energy Factor	Est. Ann. Oper Nat.	ating Cost LP
40	Tall	MV40FDVX	36	30	30.3	66	19-3/4	59-3/4	59-3/4	5	155	0.59	\$309	\$520
50	Tall	MV50FDVX	36	32	32.3	78	21-3/4	59-1/2	59-1/2	5	165	0.59	\$309	\$520

for installation with this heater.



CO-AXIAL ROOF JACK SIZING TABLE FRONT VIEW 34° MAX. (8-12 **ROOF JACK** Roof Jack PITCH) ROOF JACK **ADJUSTMENT** (Purchased Senarately) KIT PART NUMBER RANGE (SEE X) AP14363A 24 - 37 Inches Roof Jack Adjustment Range AP14363B 33 - 68 Inches AP14363C 45 - 97 Inches AP14363D 60 - 130 Inches AP14363E 72 - 160 Inches NOTE: 42° Max. adjustment roof jacks available. Roof Jacks must be ordered separately with this direct vent water heater and installed in accordance with the instructions furnished with the heater. No other roof jack or vertical vent kit is approved